

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
24 July 2003 (24.07.2003)


PCT

(10) International Publication Number
WO 03/060895 A1

- (51) International Patent Classification⁷: **G11B 7/24** (74) Agent: **DEGUELLE, Wilhelmus, H., G.**; Internationaal Octrooibureau B.V., Prof. Holstlaan 6, NL-5656 AA Eindhoven (NL).
- (21) International Application Number: PCT/IB03/00090
- (22) International Filing Date: 16 January 2003 (16.01.2003) (81) Designated States (*national*): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, OM, PH, PL, PT, RO, RU, SC, SD, SE, SG, SK, SL, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, YU, ZA, ZM, ZW.
- (25) Filing Language: English
- (26) Publication Language: English
- (30) Priority Data: 02075226.7 18 January 2002 (18.01.2002) EP
- (71) Applicant (*for all designated States except US*): **KONINKLIJKE PHILIPS ELECTRONICS N.V.** [NL/NL]; Groenewoudseweg 1, NL-5621 BA Eindhoven (NL).
- (72) Inventors; and
- (75) Inventors/Applicants (*for US only*): **TIEKE, Benno** [DE/NL]; Prof. Holstlaan 6, NL-5656 AA Eindhoven (NL). **MARTENS, Hubert, C., F.** [NL/NL]; Prof. Holstlaan 6, NL-5656 AA Eindhoven (NL).
- (84) Designated States (*regional*): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, HU, IE, IT, LU, MC, NL, PT, SE, SI, SK, TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).
- Published:
— with international search report

[Continued on next page]

(54) Title: OPTICAL DATA STORAGE MEDIUM FOR WRITE ONCE RECORDING



(57) Abstract: A dual-stack optical data storage medium (10) for write-once recording using a focused radiation beam (9) entering through an entrance face (8) of the medium is described. The medium comprises at least one substrate (1, 7) with present on a side thereof a first recording stack (2) named L_0 , comprising a write-once type L_0 recording layer (3) with an absorption k_{L0} and a second recording stack (5) named L_1 comprising a write-once type L_1 recording layer (6) with an absorption k_{L1} . The first recording stack L_0 has an optical reflection value R_{L0} and an optical transmission value T_{L0} and the second recording stack has an optical reflection value R_{L1} . The first recording stack is present at a position closer to the entrance face (8) than the second recording stack. When the following conditions are fulfilled: $0.45 = T_{L0} = 0.75$ and $0.40 = R_{L1} = 0.80$ and $k_{L0} < 0.3$ and $k_{L1} < 0.3$ a dual stack write-once medium is achieved which can be played in a standard DVD-ROM player. Several stack designs are described fulfilling the above conditions.



For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

OPTICAL DATA STORAGE MEDIUM FOR WRITE ONCE RECORDING

The invention relates to a dual-stack optical data storage medium for write-once recording using a focused radiation beam having a wavelength λ and entering through an entrance face of the medium during recording, comprising:

- at least one substrate with present on a side thereof:

5 - a first recording stack named L_0 , comprising a write-once type L_0 recording layer having a complex refractive index $\tilde{n}_{L0} = n_{L0} - i.k_{L0}$ and having a thickness d_{L0} , said first recording stack L_0 having an optical reflection value R_{L0} and an optical transmission value T_{L0} ,

10 - a second recording stack named L_1 comprising a write-once type L_1 recording layer having a complex refractive index $\tilde{n}_{L1} = n_{L1} - i.k_{L1}$ and having a thickness d_{L1} , said second recording stack L_1 having an optical reflection value R_{L1} , all parameters defined at the wavelength λ ,
said first recording stack being present at a position closer to the entrance face than the second recording stack,

15 - a transparent spacer layer sandwiched between the recording stacks, said transparent spacer layer having a thickness substantially larger than the depth of focus of the focused radiation beam.

20 An embodiment of an optical recording medium as described in the opening paragraph is known from Japanese Patent Application JP-11066622.

Recently the Digital Versatile Disk (DVD) has gained market share as a medium with a much higher data storage capacity than the CD. Presently, this format is available in a read only (ROM), recordable (R) and a rewritable (RW) version. For
25 recordable and rewritable DVD, there are at present several competing formats: DVD+R, DVD-R for recordable and DVD+RW, DVD-RW, DVD-RAM for rewritable. An issue for both the recordable and rewritable DVD formats is the limited capacity and therefore recording time because only single-stacked media are present with a maximum capacity of 4.7 GB. Note that for DVD-Video, which is a ROM disk, dual layer media with 8.5 GB

capacity, often referred to as DVD-9, already have a considerable market share.

Consequently, recordable and rewritable DVD's with 8.5GB capacity are highly desired. A dual-layer, i.e. dual-stack, rewritable DVD disk is probably feasible. However, it has become clear that a rewritable fully compatible disk, i.e. within the reflection and modulation specification of the dual-layer DVD-ROM, is very difficult to achieve and requires at least a major breakthrough for the properties of the amorphous/crystalline phase-change materials, which are used as recording layers in rewritable DVD media. Typical achievable effective reflection levels are about 7%; such low reflection values severely reduce read-back compatibility on existing DVD-players. Without a full compatibility, the success of a dual-layer rewritable DVD in the market is questionable.

In order to obtain a dual-stack recordable DVD medium which is compatible with the dual-layer (=dual-stack) DVD-ROM standard, the effective reflectivity of both the upper L_0 layer and the lower L_1 layer should be at least 18%, i.e. the minimum effective optical reflection level in order to meet the specification is $R_{\min} = 0.18$. Effective optical reflection means that the reflection is measured as the portion of effective light coming back from the medium when e.g. both stacks L_0 and L_1 are present and focusing on L_0 and L_1 respectively. The minimum reflection $R_{\min} = 0.18$ is a requirement of the DVD-standard. However, in practice also a somewhat lower effective reflection, e.g. $R > 0.12$, is acceptable to achieve read-out compatibility in existing DVD-players. Note that such a reflectivity of $R > 0.12$ is, at present, not achievable in a rewritable dual-stack DVD based on e.g. phase-change technology.

The conditions, which must be imposed on the optical reflection, absorption and transmission values of the stacks in order to meet such a specification are by far not trivial. In JP-11066622 nothing is mentioned about requirements with respect to optical reflection, absorption and transmission values of the stacks and how to achieve these. It should be noted that in this document L_0 is defined as the "closest" stack, i.e. closest to the radiation beam entrance face, and L_1 is the deepest stack, as seen from the radiation beam entrance face.

It is an object of the invention to provide a dual stack optical data storage medium of the type mentioned in the opening paragraph which has effective reflection values which provide at least read-out compatibility with existing DVD-ROM players. In an optimized form compatibility may be achieved with the existing DVD-ROM standard.

This object is achieved with the optical data storage medium according to the invention which is characterized in that $0.45 \leq T_{L0} \leq 0.75$ and $0.40 \leq R_{L1} \leq 0.80$ and $k_{L0} < 0.3$ and $k_{L1} < 0.3$. The applicant has found that these requirements may be deduced from the requirement that the effective reflection levels from both recording stacks L_0 and L_1 are
 5 larger than 12%. More preferably $0.55 \leq T_{L0} \leq 0.65$ and $0.50 \leq R_{L1} \leq 0.70$ and $k_{L0} < 0.2$ and $k_{L1} < 0.2$ in which case even higher effective reflection values may be achieved e.g. 15% or 18%. A dual-stack recordable DVD medium (e.g. DVD+R) based on a recording layer with write once technology, having a relatively low optical absorption can in principle overcome the reflection-problem of the phase-change rewritable DVD dual stack medium. A write-once
 10 recording layer with a relatively low absorption is e.g. a dye layer. The present invention can be applied to both the DVD+R and DVD-R formats. In the following, we will use DVD+R to indicate a recordable DVD in general.

The typical single stack DVD+R medium has a reflectivity of 50% and a modulation of 60%; these values are within the single stack DVD-ROM specification;
 15 DVD+RW media have much lower reflectivity of about 20%. The starting point for developing a dual-stack R-medium is thus much more favorable than for RW media. The dye material intrinsically has a high transmission at the wavelength λ . In combination with a metal reflective layer, a high reflectivity can be achieved. Thus, recording is possible with a relatively low absorption in the dye layer. Typical dyes that can be used are cyanine-type,
 20 azo-type, squarylium-type, or other organic dye material having the desired properties.

The minimum effective reflection of both layers is 12%, typical stack designs in this invention are targeted for at least $R_{eff}=18\%$. Figure 1 shows that a compatible dual stack DVD+R medium is in principle possible when assuming reasonable numbers for transmission and absorption of recording, e.g. dye, stacks. A reflection of larger than 18% per
 25 stack is possible if the transmission of the upper recording stack L_0 is between 45% and 75%; the intrinsic reflection of the lower recording stack L_1 should then be in the range 40% – 80%. Figure 1b illustrates this fact in more detail.

In the DVD embodiment λ is approximately 655 nm. Fig. 4a shows the calculated reflectivity for a recording layer-only stack as a function of the L_0 recording layer
 30 thickness d_{L0} . For common values of the recording layer's optical constants ($n_{L0} < 3$, $k_{L0} < 0.3$) a sufficiently high transmission can be achieved; the reflectivity therefore determines the required optical parameters and layer thickness. Preferably $n_{L0} \geq 2.5$ and d_{L0} is in the range of $\sqrt{8}n_{L0} \leq d_{L0} \leq 3\sqrt{8}n_{L0}$ or $5\sqrt{8}n_{L0} \leq d_{L0} \leq 7\sqrt{8}n_{L0}$. Fig 4b shows the calculated maximum reflectivity of a L_0 recording layer-only stack as a function of the real part of the refractive

index n_{L0} of the recording layer; the dashed horizontal line indicates a reflection level $R = 18\%$. It follows from Figure 4b that in order to get a reflectivity of at least 18%, the recording layer's refractive index n_{L0} should be sufficiently large (or small):

$$n_{L0} \geq 2.5 \quad \text{or} \quad n_{L0} \leq 1.0$$

5 The latter is however less likely to be met in practice.

The optimal L_0 recording layer thickness d_{L0} is at the first or second maximum in reflectivity, the preferred layer thickness is then:

$$\lambda/8n_{L0} \leq d_{L0} \leq 3\lambda/8n_{L0} \quad (1^{\text{st}} \text{ max})$$

$$5\lambda/8n_{L0} \leq d_{L0} \leq 7\lambda/8n_{L0} \quad (2^{\text{nd}} \text{ max})$$

10 The advantages of this L_0 stack design are a high transparency and its simplicity.

In another embodiment a first metal reflective layer, having a thickness $d_{M1} \leq 25$ nm, is present between the write-once L_0 recording layer and the transparent spacer layer and d_{L0} is in the range of $\lambda/8n_{L0} \leq d_{L0} \leq 5\lambda/8n_{L0}$. For this stack, a relatively thin first metal reflective layer is placed between the dye and the spacer. The first metal reflective layer serves as a semi-transparent layer to increase the reflectivity. A maximum thickness and suitable material must be specified to keep the transmission of the first metal reflective layer sufficiently high. For the metal layer e.g. Ag, Au, Cu, Al, or alloys thereof, or doped with other elements, can be used. In order to obtain a sufficiently transparent stack ($T_{L0} \geq 45\%$), the preferred thickness of the metal layer is:

20
$$d_{M1} \leq 25 \text{ nm}$$

The optimum dye-layer thickness is determined by both the maxima in transmission and reflection.

The presence of the thin metal layer introduces an additional phase shift $\Delta \sim 1/8$ to $1/4$ in the extrema of R and T ; for this stack design the maxima in R and T are located at: $\text{Max}(R) \rightarrow \lambda/2n_{L0} (p - \Delta)$, $\text{Max}(T) \rightarrow \lambda/2n_{L0} (p + 1/2 - \Delta)$.

Only the thickness range around the first reflection maximum is suitable because of the decreasing transmission for larger dye thickness. The lower limit (LL) for d_{L0} is defined by the maximum in T : $\text{LL} = \text{Max}(R) - 1/2 \text{ period} = \lambda/8n_{L0}$. The upper limit for d is defined by $2^{\text{nd}} \text{ Max}(T) - 1/8 \text{ period} = \text{Max}(R) + 3/8 \text{ period} = 5\lambda/8n_{L0}$ because for increasing thickness the reflectivity drops strongly. Thus, the preferred dye layer thickness range becomes:

$$\lambda/8n_{L0} \leq d_{L0} \leq 5\lambda/8n_{L0}.$$

The advantages of the described design are the good reflective properties and the nearly similar stack design, and thus nearly similar fabrication process, as "standard" single recording stack medium.

In another embodiment a first transparent auxiliary layer I1, having a refractive index $n_{I1} \geq 1.8$ and having a thickness $d_{I1} \leq \lambda/2n_{I1}$, is present between the first metal reflective layer and the transparent spacer layer. By adding a first transparent auxiliary layer I1, e.g. a dielectric interference layer, adjacent the first metal reflective layer the transmission near the optimum reflectivity is increased; the role of the dielectric I-layer is to counteract the optical mismatch between the "recording layer + thin metal" stack and the substrate, e.g. made of polycarbonate, and thereby lower the reflection and raise the transmission.

Clearly, with three layers many combinations are possible. However, the only useful stack design is recording layer/thin-metal/I-layer, which can have high T, finite R, and sufficient absorption in the recording layer at the same time. For this stack type, for the first metal reflective layer e.g. Ag, Au, Cu, Al or alloys thereof, or doped with other elements, can be used. In order to obtain a sufficiently transparent stack, the preferred thickness of the metal layer for this stack type is:

$$d_{M1} \leq 25 \text{ nm}$$

As shown in Fig 10, the first auxiliary layer I1 below the first metal reflective layer indeed increases the stack's transmission and decreases its reflectivity, while the position of the R- and T-extrema stays (nearly) the same. The optimum recording layer thickness is determined by the first maximum in reflection, which is given by $\text{Max}(R) \rightarrow \lambda/2n_{L0} (1 - \Delta)$, where $\Delta \sim 1/8$ to $1/4$ is a phase shift introduced by the metal. The preferred recording layer thickness for this stack becomes:

$$\lambda/8n_{L0} \leq d_{L0} \leq 5\lambda/8n_{L0}$$

It is preferred that $d_{I1} \leq \lambda/4n_{I1}$. It appears that the relative increase in T that can be gained by the first auxiliary I1-layer depends on the I1-layer's refractive index and on the metal reflective layer thickness, while the properties of the recording layer do not influence the relative increase of T. As shown in Fig 11, the useful range of refractive indices n_I of the I-layer is

$$n_{I1} \geq 1.8$$

From Fig 11 it can be derived what the minimal refractive index of the I1-layer is for which an increase by a factor X in transmission of the bare recording layer/thin-

metal-reflective layer stack can be gained. It follows that for an X-gain in transmission the I-layer's refractive index should be:

$$n_{I1} \geq (X + 0.036 \cdot d_{M1} - 1.025) / (0.0267 \cdot d_{M1} + 0.005)$$

Here, the first metal reflective layer thickness d_{M1} is given in nanometers (note
 5 that the formula is an approximation in the range of n_{I1} of 1.8 – 3). The X-factor can be calculated by dividing the required transmission of the stack (e.g. 50 %) by the transmission of the bare (without I-layer) recording layer/thin-metal-reflective layer stack (e.g. 38%). For example, if a transmission increase by a factor $50/38 = 1.3$ is required for the bare recording layer/thin-metal-reflective layer stack having a metal reflective layer of 15 nm thickness, the
 10 refractive index of the additional I1-layer should be at least 2.0.

The reflection and transmission of the stack are also periodic in the thickness of the lower-lying interference layer, with period $\lambda/2n_{I1}$. Therefore, the I1-layer thickness need not be larger than one period:

$$d_{I1} \leq \lambda/2n_{I1}$$

15 If the I1-layer is intended to increase T (and decrease R) it's optimal thickness lies at the position of the first maximum in T which is located at $(1/2 - \Delta) \cdot \lambda/2n_{I1}$, with $\Delta \sim 1/8$.

The preferred (optimal) thickness of the I-layer then becomes:

$$d_{I1, \text{opt}} = 3\lambda/16n_{I1}$$

20 For larger d_{I1} the transmission decreases and the reflection increases again. If n_{I1} is sufficiently large, it is possible to keep the I1-layer's thickness below the optimum value given above.

The useful thickness range of the I-layer then becomes:

$$d_{I1} \leq \lambda/4n_{I1}$$

25 The advantage of this design is its flexibility, i.e. a large range of R and T is possible.

In another embodiment a second transparent auxiliary layer I2, having a refractive index n_{I2} and having a thickness d_{I2} in the range of $0 < d_{I2} \leq 3\lambda/8n_{I2}$, is present at a side of the write-once L_0 recording layer and d_{L0} is in the range of $\lambda/8n_{L0} \leq d_{L0} \leq 3\lambda/8n_{L0}$ or $5\lambda/8n_{L0} \leq d_{L0} \leq 7\lambda/8n_{L0}$. Preferably the second transparent auxiliary layer is present at a side
 30 of the write-once L_0 recording layer most remote from the entrance face and $n_{I2} \leq n_{L0}/1.572$. Alternatively the second transparent auxiliary layer is present at a side of the write-once L_0 recording layer closest to the entrance face and $n_{I2} \geq n_{L0}/0.636$. No metal reflective layer is present. This stack is based on the principle of a dielectric mirror. Since the second auxiliary

I2-layer, i.e. the dielectric mirror, is transparent, the requirements for recording- and I-layer thickness and optical constants follow from the reflectivity constraint.

The reflectivity is maximized when the interference layer is $\lambda/4n_{I2}$ (or $3\lambda/4n_{I2}$) thick and the dye layer $\lambda/4n_{L0}$ (1st max) or $3\lambda/4n_{L0}$ (2nd max).

- 5 The preferred range of the interference layer thickness is:

$$0 < d_{I2} \leq 3\lambda/8n_{I2}$$

The preferred thickness range for the dye layer is:

$$\lambda/8n_{L0} \leq d_{L0} \leq 3\lambda/8n_{L0} \text{ (1st max)}$$

$$5\lambda/8n_{L0} \leq d_{L0} \leq 7\lambda/8n_{L0} \text{ (2nd max)}$$

- 10 Two cases of this type of stack can be discerned:

- (a) recording layer on top of I2-layer and
- (b) I2-layer on top of recording layer.

Case (a):

The optimum reflectivity is given by $R = [(1 - (n_{L0}/n_{I2})^2)/(1 + (n_{L0}/n_{I2})^2)]^2$.

- 15 To meet the reflectivity specification of $R = 18\%$, the I2-layer's refractive index can be calculated to be:

$$n_{I2} \leq n_{L0}/1.572$$

Case (b):

The optimum reflectivity is given by $R = [(1 - (n_{I2}/n_{L0})^2)/(1 + (n_{I2}/n_{L0})^2)]^2$.

- 20 To meet the reflectivity specification of $R = 18\%$, the I2-layer's refractive index can be calculated to be:

$$n_{I2} \geq n_{L0}/0.636$$

- 25 By adding more transparent auxiliary layers (with alternating high n and low n , and thickness around $\lambda/4n$) the reflective properties of the stack can be improved using less extreme values of the refractive indices of the I2-layers. However, the stack becomes more complicated then. The advantage of the design described above is its relative simplicity while still sufficient reflection and high transmission are achieved.

The stacks proposed for L_0 are not restricted to use in dual-stack media, but can be used in single-stack and multi-stack (>2) media as well.

- 30 For the L_1 stack of the dual-stack optical data storage medium according to the invention a second metal reflective layer is present at a side of the write-once type L_1 recording layer most remote from the entrance face. In another embodiment the second metal reflective layer has a thickness $d_{M2} \geq 25$ nm and preferably d_{L1} is in the range of $0 < d_{L1} \leq 3\lambda/4n_{L1}$. The latter range is the range of a conventional single stack write once medium.

When d_{M2} is lower than 25 nm the reflectivity may become too low. The lower L_1 stack of a recordable dual-stack DVD medium should have high reflectivity at the radiation beam wavelength in order to be able to read back recorded data through the above L_0 stack. To meet the DVD-ROM dual-layer (i.e. dual-stack) specifications the effective reflectivity of L_1 should be in the range of 18% to 30%. If the L_0 stack has a transmission at the laser wavelength of T_{L1} , this means that the intrinsic reflection of L_1 should be in the range $18/T_{L0}^2$ % to $30/T_{L0}^2$ %. Given typical transmission of L_0 in the range 50% to 60%, this implies that L_1 's reflectivity should be 50% or more. This value already falls within the reflectivity-range specified for single-stack DVD+R discs. Thus in principle a single-stack DVD+R stack design can be used as the L_1 -stack. However, in the case of type 2 (see Fig. 16b) discs, this implies that the recording layer, e.g. the dye is in direct contact with e.g. the adhesive for the spacer layer. This adhesive can possibly harm the dye, resulting in poor medium lifetimes.

It is therefore preferred that a third transparent auxiliary layer I_3 , having a refractive index n_{I3} and having a thickness d_{I3} in the range $0 < d_{I3} \leq \lambda/n_{I3}$, is present adjacent the write-once type L_1 recording layer at a side of the write-once type L_1 recording layer closest to the entrance face or that a third metal reflective layer, having a thickness d_{M3} in the range of $0 < d_{M3} \leq 25$ nm, is present adjacent the write-once L_1 recording layer at a side closest to the entrance face and d_{L1} is in the range of $0 < d_{L1} \leq 5\lambda/16n_{L1}$ or $7\lambda/16n_{L1} \leq d_{L1} \leq \lambda/n_{L1}$. By introducing the third transparent auxiliary layer or third metal reflective layer the problem of chemical influence of the spacer layer to the recording layer is counteracted. Two L_1 stack types are proposed here which protect the recording layer from e.g. the adhesive of the spacer layer. The stacks proposed here are not restricted to use in dual-stack optical recording media and can be applied in any (single-stack and multi-stack) organic-recording layer, e.g. dye, based optical recording medium. For the third metal reflective layer e.g. Ag, Au, Cu, Al or alloys thereof, or doped with other elements, can be used.

Schematic layout of this stack design is given in Fig. 14.

For the thin metal layer e.g. Ag, Au, Cu, Al or alloys thereof, or doped with other elements, can be used.

In an advantageous embodiment of the dual-stack optical data storage medium a fourth transparent auxiliary layer I_4 , having a refractive index n_{I4} and having a thickness d_{I4} in the range of $0 < d_{I4} \leq 3\lambda/16n_{I4}$, is present between the write-once L_1 recording layer and the second metal reflective layer. This fourth transparent auxiliary layer allows a slightly thinner recording layer thickness, while the reflection and modulation of written marks remains good.

In yet another advantageous embodiment of the dual-stack optical data storage medium a fifth transparent auxiliary layer I5, having a refractive index n_{I5} and having a thickness d_{I5} in the range of $0 < d_{I5} \leq \lambda/4n_{I5}$, is present adjacent the third metal reflective layer at a side of the third metal reflective layer closest to the entrance face. This fifth transparent auxiliary layer increases the chemical barrier between the recording layer and the spacer-layer adhesive that is beneficial for lifetime of the recording stack.

It may be advantageous when at least one of the transparent auxiliary layers comprises a transparent heatsink material selected from the group of materials ITO, HfN and AlON. Generally dielectric materials exhibit a poor heat conductivity. The mentioned materials have a relatively high heat conductivity while they are transparent. A high heat conductivity may increase the quality of recorded marks in terms of mark definition, e.g. jitter, shape, modulation

In the dual stack optical data storage medium a guide groove for L_1 may be provided in the transparent spacer layer, called type 1, or in the substrate, called type 2. The guide groove is also called pregroove or servo groove. A guide groove for L_0 may be provided in the substrate closest to the entrance face.

The invention will be elucidated in greater detail with reference to the accompanying drawings, in which:

Figure 1a shows the maximum attainable effective reflection of both the upper recording stack L_0 and the lower recording stack L_1 as a function of the transmission of upper recording stack L_0 ;

Figure 1b shows the effective total reflection from the L_1 stack as a function of the intrinsic reflection of L_1 ; examples for three different Transmission values of L_0 are shown;

Figure 2 shows a schematic layout of an embodiment of the optical data storage medium according to the invention including the two stacks L_0 and L_1 ;

Figure 3 shows a schematic layout of an embodiment of the L_0 stack of the optical data storage medium (recording layer-only L_0 stack design);

Figure 4a shows the calculated reflectivity as a function of the recording layer thickness d_{L0} for three values of the recording layer refractive index n_{L0} .

Figure 4b shows the maximally attainable reflectivity of a single recording layer in an optical data storage medium;

Figure 5 shows a schematic layout of another embodiment of the L_0 stack of the optical data storage medium;

Figure 6a shows a graph of the transmission of the stack of Fig. 5 as a function of the recording layer thickness for three values of the refractive index of the recording layer.

5 The dashed line indicates the lower limits allowed for T;

Figure 6b shows the reflection of these same stacks as function of the recording layer thickness;

Figure 7a shows a schematic layout of another embodiment of the L_0 stack of the optical data storage medium;

10 Figure 7b shows a schematic layout of another embodiment of the L_0 stack of the optical data storage medium;

Figure 8a shows the maximum reflectivity of a recording layer/auxiliary layer stack as a function of the refractive index n_I of the auxiliary layer I for five values of the recording layer's refractive index n_{L0} ;

15 Figure 8b shows the maximum reflectivity of an auxiliary layer/recording layer stack as a function of the refractive index n_I of the auxiliary layer I for five values of the recording layer's refractive index n_{L0} ;

Figure 9 shows a schematic layout of another embodiment of the L_0 stack of the optical data storage medium;

20 Figure 10a shows a comparison between the transmission of a recording layer/thin-metal reflective layer stack and a recording layer/thin-metal reflective layer/auxiliary-layer stack as a function of the recording layer thickness;

Figure 10b shows the same for reflection as a function of the recording layer thickness for the stacks of Fig. 10a.

25 Figure 11 shows the maximum factor (X) by which the transmission of a recording layer/thin-metal reflective layer stack can be increased when adding an auxiliary I-layer adjacent the metal reflective layer;

Figure 12 shows a schematic layout of an embodiment of the L_1 stack of the optical data storage medium design: auxiliary layer/ recording layer/ relatively thick metal reflective layer.

30 Figure 13 shows the intrinsic reflection of the L_1 stack design of Fig 12 as a function of the recording layer thickness ($k_{L1}=0.1$) for three values of the refractive index n_{L1} of the recording layer. The dashed line indicates the 50% reflection level, which is a practical lower limit for the L_1 intrinsic reflectivity.

Figure 14 shows a schematic layout of another embodiment of the L_1 stack of the optical data storage medium (design: thin metal layer/ recording layer/ relatively thick metal layer).

Figure 15 shows the intrinsic reflection of the L_1 stack design of Fig. 14 as a function of the recording thickness;

Figure 16a shows a type 1 optical data storage medium;

Figure 16b shows a type 2 optical data storage medium.

In Fig. 1a the maximum attainable reflection of the lower recording stack L_1 as a function of the transmission T of upper recording stack L_0 is shown. The lines for absorption $A=0$ are the theoretical limit, a typical absorption for e.g. a dye layer would be 10%. The effective reflection of 18% per stack as required by the DVD standard is indicated by the horizontal dashed line; in this invention $R_{\text{eff}} \geq 18\%$ is taken as a targeted value for the preferred embodiments.

In Fig. 1b the effective total reflection from the L_1 stack as a function of the intrinsic reflection of L_1 is drawn. Examples for three different transmission values T of the L_0 stack are shown;

In Fig 2 a dual-stack optical data storage medium 10 for recording using a focused laser beam 9 having a wavelength 655 nm is shown. The laser beam 9 enters through an entrance face 8 of the medium 10 during recording. The medium 10 comprises a substrate 7 with present on a side thereof a first recording stack 5 named L_0 , comprising a write-once type L_0 recording layer 6 having a complex refractive index $\tilde{n}_{L0} = n_{L0} - i.k_{L0}$ and having a thickness d_{L0} . The first recording stack L_0 has an optical reflection value R_{L0} and an optical transmission value T_{L0} . A second recording stack 2 named L_1 comprising a write-once type L_1 recording layer 3 having a complex refractive index $\tilde{n}_{L1} = n_{L1} - i.k_{L1}$ and having a thickness d_{L1} is present. The second recording stack L_1 has an optical reflection value R_{L1} . The optical parameters are all measured at the laser beam wavelength. The first recording stack 5 is present at a position closer to the entrance face 8 than the second recording stack 3. A transparent spacer layer 4 is sandwiched between the recording stacks 2 and 5. The transparent spacer layer 4 has a thickness substantially larger than the depth of focus of the focused radiation beam 9.

To meet the DVD-ROM dual layer specification, the effective reflection level from the upper recording stack L_0 , being equal to R_{L0} , and the effective reflection level from

the lower recording stack L_1 , being equal to $R_{L1} \cdot (T_{L0})^2$, should both fall in the range 18% to 30%: $0.18 \leq R_{L0} \leq 0.30$ and $0.18 \leq R_{L1} \cdot (T_{L0})^2 \leq 0.30$. In practice, effective reflection levels > 12% are sufficient for read-out compatibility on existing DVD players. Practical ranges of T_{L0} and R_{L1} for which the latter condition can be achieved, are: $0.45 \leq T_{L0} \leq 0.75$ and $0.40 \leq R_{L1} \leq 0.80$ and $k_{L0} < 0.3$ and $k_{L1} < 0.3$. Thus, with the proper combination of R_{L0} , T_{L0} and R_{L1} a DVD+R dual layer (DL) medium is achieved compatible with the DVD-ROM dual layer specification as far as reflection levels are concerned. A DVD+R DL disc could consist of any combination of L_0 -stack and L_1 -stack. One specific embodiment would be:

Medium of type 2 (see Fig 16b), with L_0 embodiment stack 5 (95 nm dye/ 10 nm Ag/ 55 nm ZnS-SiO₂) and L_1 embodiment stack 3 (15 nm Ag/ 130 nm dye/ 100 nm Ag), having transparent spacer 4 thickness of 55 μ m. Effective reflection from L_0 is 28 %, effective reflection (through L_0) from L_1 is 21%. By using dyes as recording layer, which dyes are almost transparent at the laser recording wavelength, recording stacks with high transmission suitable for multi-stack media can be fabricated. This is typically the case in write-once optical media such as CD-R and DVD+R. Below follow different L_0 stack designs, in which an organic dye is incorporated. The designs have a high transparency (in order to enable addressing lower-lying stacks) and finite reflectivity (necessary for read-out). The parameter ranges are tuned such as to meet the specifications for the upper recording stack L_0 in a recordable dual-stack DVD disc:

$$R_{L0} \geq 18 \%,$$

$$T_{L0} \geq 50 \%.$$

The lower limit for T_{L0} may be lower, e.g. 45%, if L_1 is very highly reflective. To understand the thickness ranges proposed for the different stacks below, it is helpful to note that:

- (i) The reflection and transmission of the stacks are periodic in $\lambda/2n$.
- (ii) The extrema in reflection and transmission of the stacks nearly coincide due to the intrinsic high transparency of the recording layer, e.g. dyes ($k < n$).

In Fig. 3 an embodiment of the L_0 stack of the dual-stack optical data storage medium 10 is shown having a recording layer 6 wherein $n_{L0} \geq 2.5$ and d_{L0} is in the range of $\lambda/8n_{L0} \leq d_{L0} \leq 3\lambda/8n_{L0}$ or $5\lambda/8n_{L0} \leq d_{L0} \leq 7\lambda/8n_{L0}$. The symbols have the meaning as described with Fig.2. The recording layer 6 is a 59 nm thick azo-dye having a refractive index $\tilde{n}_{L0} = 2.68 - i.0.23$. The reflection $R_{L0} = 0.18$ and the transmission $T_{L0} = 0.58$. The wavelength λ is 655nm.

In Fig. 4a the calculated reflectivity as a function of the recording layer 6 thickness d_{L0} for three values of the recording layer's refractive index n_{L0} is drawn. Notice

that a reflection level of more than 0.18 can be achieved when the recording layer 6 has a refractive index n_{L0} larger than 2.5. The optima in reflection are located at thickness of $(\frac{1}{2} + p) \cdot \lambda / 2nd$, with p an integer.

In Fig. 4b the maximally attainable reflectivity of a single recording layer in an optical data storage medium (recording layer is embedded in polycarbonate background having a refractive index $n = 1.6$) is shown. The dashed line indicates the value $R = 18\%$.

In Fig. 5 an embodiment of the L_0 stack of the dual-stack optical data storage medium 10 is shown having a recording layer 6 wherein a first metal reflective layer 11, having a thickness $d_{M1} \leq 25$ nm, is present between the write-once L_0 recording layer 6 and the transparent spacer layer 4 and d_{L0} is in the range of $\lambda / 8n_{L0} \leq d_{L0} \leq 5\lambda / 8n_{L0}$. The symbols have the meaning as described with Fig. 2. The recording layer 6 is a 100 nm thick azo-dye (JJAP 37 (1998) 2084) having a refractive index $\tilde{n}_{L0} = 2.44 - i0.06$. The wavelength λ of the focused laser beam 9 is 655 nm.

The following results may be obtained when the first metal reflective layer 11 is:

-8 nm Ag ($n=0.16$, $k=5.34$) $R_{L0} = 0.21$, $T_{L0} = 0.53$

-10 nm Au ($n=0.28$, $k=3.9$) $R_{L0} = 0.27$, $T_{L0} = 0.52$

-10 nm Cu ($n=0.23$, $k=3.7$) $R_{L0} = 0.25$, $T_{L0} = 0.55$

In Fig. 6a a calculated graph of the transmission T_{L0} of the stack of Fig. 5 as a function of the recording layer 6 thickness d_{L0} for three values of the refractive index n_{L0} of the recording layer 6 is shown. The first metal reflective layer 11 is 10 nm Ag. The dashed line indicates the 50% value for T .

In Fig. 6b the calculated reflection R_{L0} of this same stack as function of the recording layer 6 thickness d_{L0} is shown. The dashed red line indicates the lower limits allowed for R . The maxima in R and minima in T are located at thickness $(p - \Delta) \cdot \lambda / 2nd$, where p is an integer and $\Delta \sim 1/8$ to $1/4$. The minima in R and maxima in T are located at thickness $(p + \frac{1}{2} - \Delta) \cdot \lambda / 2nd$.

In Fig. 7a and 7b two embodiments of the L_0 stack of the dual-stack optical data storage medium are shown wherein a second transparent auxiliary layer I2 with reference numeral 12, having a refractive index n_{I2} and having a thickness d_{I2} in the range of $0 < d_{I2} \leq 3\lambda / 8n_{I2}$, is present adjacent the write-once L_0 recording layer 6 and d_{L0} is in the range of $\lambda / 8n_{L0} \leq d_{L0} \leq 3\lambda / 8n_{L0}$ or $5\lambda / 8n_{L0} \leq d_{L0} \leq 7\lambda / 8n_{L0}$. In Fig. 7a the second transparent auxiliary layer 12 is present at a side of the write-once L_0 recording layer 6 most remote from the entrance face 8 and $n_{I2} \leq n_{L0} / 1.572$. The second transparent auxiliary layer I2 is a

dielectric layer made of SiO₂ with a refractive index $n_{L2} = 1.44$ and a thickness $d_{L2} = 114$ nm. The recording layer 6 is an azo-dye (JJAP 37 (1998) 2084) having a refractive index $\tilde{n}_{L0} = 2.44 - i.0.06$ and a thickness $d_{L0} = 67$ nm. The wavelength λ of the focused laser beam 9 is 655nm. The following reflection and transmission may be obtained: $R_{L0} = 0.20$, $T_{L0} = 0.72$.

5 In Fig.8a the maximum reflectivity of a recording layer/auxiliary layer stack is shown as a function of the refractive index n_I of the auxiliary layer I for five values of the recording layer's refractive index n_{L0} is shown. The dashed line indicates the 18% value for R.

10 In Fig 8b the maximum reflectivity of an auxiliary layer/recording layer stack as a function of the refractive index n_I of the auxiliary layer I for five values of the recording layer's refractive index n_{L0} is shown. The dashed line indicates the 18% value for R.

In Fig. 9 an embodiment of the L₀ stack of the dual-stack optical data storage medium 10 is shown as in Fig. 5 wherein additionally a first transparent auxiliary layer 13 (I₁), having a refractive index $n_{I1} \geq 1.8$ and having a thickness $d_{I1} \leq \sqrt{2}n_{I1}$, is present between 15 the first metal reflective layer 11 and the transparent spacer layer 4. Preferably $d_{I1} \leq \sqrt{4}n_{I1}$. The symbols have the meaning as described with Fig.2. The recording layer 6 is a 95 nm thick azo-dye (JJAP 37 (1998) 2084) having a refractive index $\tilde{n}_{L0} = 2.44 - i.0.06$. The wavelength λ of the focused laser beam 9 is 655nm.

20 The following results may be obtained when the first metal reflective layer 11 and the first auxiliary layer 13 respectively are:

-10 nm Ag ($n=0.16$, $k=5.34$) and 55 nm (ZnS)₈₀(SiO₂)₂₀ ($n=2.15$): $R_{L0} = 0.28$, $T_{L0} = 0.53$
 -10 nm Cu ($n=0.23$, $k=3.7$) and 20 nm (ZnS)₈₀(SiO₂)₂₀: $R_{L0} = 0.19$, $T_{L0} = 0.62$.

25 In Fig.10a a comparison between the transmission of a recording layer/thin-metal reflective layer stack ($n_{L0} = 2.4$, $k_{L0} = 0.1$, 10 nm Ag) and a recording layer/thin-metal reflective layer/auxiliary-layer stack ($n_{L0} = 2.4$, $k_{L0} = 0.1$, 10 nm Ag, $n_I = 2.1$, $d_I = 50$ nm) as a function of the recording layer thickness d_{L0} is shown. The dashed line indicates the 50% value for T.

In Fig.10b the reflection as a function of the recording layer thickness d_{L0} for the stacks of Fig.10a is shown. The dashed line indicates the 18% value for R.

30 In Fig.11 the maximum factor (X) by which the transmission of a recording layer/thin-metal reflective layer stack can be increased when adding an auxiliary I-layer adjacent the metal reflective layer as a function of the refractive index of the I-layer for three values of metal layer thickness. The dashed lines indicate linear approximations of the functions $X(n_I)$ in the range $1.8 \leq n_I \leq 3.0$.

It may be advantageous to apply a transparent heat sink in the L_0 recording stack instead of or in addition to the auxiliary layer(s). This may lead to improved recording performance due to heat sink action. The types of L_0 stack that can be used have been described with Fig 7 and Fig. 9. In these two stack types an auxiliary, i.e. dielectric layer, is present to tune the reflection and transmission values. Typical dielectric materials used are ZnS-SiO₂ or SiO₂, etc. These dielectric materials have poor heat conductivity, typically < 1 W/mK. An improved heat sink function can be obtained by replacing the dielectric with for instance ITO, HfN, or AlON which have a heat conductivity > 1 W/mK (ITO has about 3.6 W/mK). These materials have optical constants close to typical dielectrics ($n \sim 2$, $k < 0.05$), therefore optical stack designs similar to those of e.g. Fig. 7 and Fig. 9 can be used.

In Fig.12 a schematic layout of an embodiment of the L_1 stack of the optical data storage medium 10 is shown. The symbols have the meaning as described with Fig.2. A second metal reflective layer 15 is present at a side of the write-once type L_1 recording layer 3 most remote from the entrance face 8. The second metal reflective layer 15 has a thickness $d_{M1} \geq 25$ nm and d_{L1} is in the range of $0 < d_{L1} \leq 3\lambda/4n^{L1}$. A third transparent auxiliary layer 16 (I3), having a refractive index n_{I3} and having a thickness d_{I3} in the range $0 < d_{I3} \leq \lambda/n_{I3}$, is present adjacent the write-once type L_1 recording layer 3 at a side of the write-once type L_1 recording layer 3 closest to the entrance face 8.

R_{L1} is the intrinsic reflection of the L_1 stack. The effective reflection as defined in annex D of the DVD read-only-disk book should be in the range $18\% \leq R_{L1eff} \leq 30\%$

T_{L0} is the intrinsic transmission of the L_0 stack, i.e. for the lower lying L_1 stack having intrinsic reflection R_{L1} the effective reflection in a true dual-stack medium will be

$$T_{L0}^2 \cdot R_{L1}$$

The recording layer 3 is a 130 nm thick azo-dye (mat sc. and eng. B79 (2001) 45.) having a refractive index $\tilde{n}_{L0} = 2.44 - i.0.06$. The wavelength λ of the focused laser beam 9 is 655nm. The fourth transparent auxiliary layer 16 is 50 nm SiO₂ ($n = 1.44$) and the second metal reflective layer is 100 nm Ag. A reflection $R_{L1} = 0.73$ is achieved.

Figure 13 shows the intrinsic reflection of the L_1 stack design of Fig 12 as a function of the recording layer thickness ($k_{L1} = 0.1$) for three values of the refractive index n_{L1} of the recording layer. The dashed line indicates the 50% reflection level, which is a practical value for the L_1 intrinsic reflectivity.

In Fig.14 a schematic layout of an embodiment of the L_1 stack of the optical data storage medium 10 is shown. The symbols have the meaning as described with Fig.2. A third metal reflective layer 17, having a thickness d_{M3} in the range of $0 < d_{M3} \leq 25$ nm, is present at a side of the write-once L_1 recording layer 3 closest to the entrance face 8 and d_{L1} is in the range of $0 < d_{L1} \leq 5\lambda/16n_{L1}$ or $7\lambda/16n_{L1} \leq d_{L1} \leq \lambda/n_{L1}$.

The second metal reflective layer 15 has a thickness $d_{M1} \geq 25$ nm. R_{L1} is the intrinsic reflection of the L_1 stack. The effective reflection as defined in annex D of the DVD read-only-disk book should be in the range $18\% \leq R_{L1\text{eff}} \leq 30\%$. T_{L0} is the intrinsic transmission of the L_0 stack, i.e. for the lower lying L_1 stack having intrinsic reflection R_{L1} the effective reflection in a true dual-stack medium will be $T_{L0}^2 \cdot R_{L1}$.

The recording layer 3 is a 150 nm thick azo-dye (JJAP 37 (1998) 2084.) having a refractive index $\tilde{n}_{L0} = 2.44 - i.0.06$. The wavelength λ of the focused laser beam 9 is 655nm. The third metal reflective layer 17 is 15 nm Ag. A reflection $R_{L1} = 0.8$ is achieved.

In another embodiment (not drawn) a fourth transparent auxiliary layer I4, having a refractive index n_{I4} and having a thickness d_{I4} in the range of $0 < d_{I4} \leq 3\lambda/16n_{I4}$, may be present between the write-once L_1 recording layer and the second metal reflective layer 15. In the latter case the recording layer 3 is a 55 nm thick azo-dye (JJAP 37 (1998) 2084.) having a refractive index $\tilde{n}_{L0} = 2.44 - i.0.06$. The wavelength λ of the focused laser beam 9 is 655nm. The third metal reflective layer 17 is 10 nm Au. The fourth transparent auxiliary layer is 60 nm SiO_2 . A reflection $R_{L1} = 0.63$ is achieved.

In Fig. 15 the intrinsic reflection of the L_1 stack design of Fig. 14 as a function of the recording thickness ($k_{L1} = 0.1$) for three values of the refractive index n_{L1} of the recording layer is shown. The dashed line indicates the 50% reflection level, which is a practical lower limit for the L_1 intrinsic reflectivity.

In Fig 16a a so-called type 1 medium is described. An optical recording stack (L_0), optically semi-transparent at the laser wavelength, is applied to a transparent, pre-grooved substrate 7. A transparent spacer layer 4 is attached to the L_0 stack. The spacer layer 4 either contains pregrooves (G) for L_1 or pregrooves (G) for L_1 are mastered into the spacer layer 4 after application to L_0 . Second recording stack L_1 is deposited on the grooved spacer layer 4. Finally, a counter substrate 1 is applied.

In Fig. 16b a so-called type 2 medium is described. An optical recording stack (L_0), optically semi-transparent at the laser wavelength, is applied to a transparent, pre-grooved substrate 7. A second optical recording stack L_1 , reflective at the laser wavelength, is applied to a second transparent pre-grooved (G) substrate 1. This substrate 1 with L_1 is

attached to the substrate 7 with L_0 with a transparent spacer layer 4 in between. Preferred spacer-layer thickness for both disc types is $40\text{ }\mu\text{m}$ to $70\text{ }\mu\text{m}$.

The stacks proposed in this document are not restricted to use in DVD+R-DL and can be applied in any (multi-stack) organic-dye based optical recording medium. The thickness and optical constant ranges specified, however, are such as to meet the requirements for an L_0 - and L_1 -stack of a DVD+R-DL medium. It should be noted that the actual recording of marks does not necessarily take place in the groove G but may take place in the area between grooves, also referred to as on-land. In this case the guide groove G merely serves as a servo tracking means with the actual radiation beam recording spot being present on-land.

It should be noted that the above-mentioned embodiments illustrate rather than limit the invention, and that those skilled in the art will be able to design many alternative embodiments without departing from the scope of the appended claims. In the claims, any reference signs placed between parentheses shall not be construed as limiting the claim. The word "comprising" does not exclude the presence of elements or steps other than those listed in a claim. The word "a" or "an" preceding an element does not exclude the presence of a plurality of such elements. The mere fact that certain measures are recited in mutually different dependent claims does not indicate that a combination of these measures cannot be used to advantage.

According to the invention a dual-stack optical data storage medium for write-once recording using a focused radiation beam entering through an entrance face of the medium is described. The medium comprises at least one substrate with present on a side thereof a first recording stack named L_0 , comprising a write-once type L_0 recording layer with an absorption k_{L0} and a second recording stack named L_1 comprising a write-once type L_1 recording layer with an absorption k_{L1} . The first recording stack L_0 has an optical reflection value R_{L0} and an optical transmission value T_{L0} and the second recording stack has an optical reflection value R_{L1} . The first recording stack is present at a position closer to the entrance face than the second recording stack. When the following conditions are fulfilled: $0.45 \leq T_{L0} \leq 0.75$ and $0.40 \leq R_{L1} \leq 0.80$ and $k_{L0} < 0.3$ and $k_{L1} < 0.3$ a dual stack write-once medium is achieved which can be played in a standard DVD-ROM player. Several stack designs are described fulfilling the above conditions.

CLAIMS:

1. A dual-stack optical data storage medium (10) for write-once recording using a focused radiation beam (9) having a wavelength λ and entering through an entrance face (8) of the medium (10) during recording, comprising:
 - at least one substrate (1, 7) with present on a side thereof:
 - 5 - a first recording stack (2) named L_0 , comprising a write-once type L_0 recording layer (3) having a complex refractive index $\tilde{n}_{L0} = n_{L0} - i.k_{L0}$ and having a thickness d_{L0} , said first recording stack L_0 having an optical reflection value R_{L0} and an optical transmission value T_{L0} ,
 - a second recording stack (5) named L_1 comprising a write-once type L_1 recording layer (6) having a complex refractive index $\tilde{n}_{L1} = n_{L1} - i.k_{L1}$ and having a thickness d_{L1} , said second recording stack L_1 having an optical reflection value R_{L1} , all parameters defined at the wavelength λ ,
 said first recording stack being present at a position closer to the entrance face than the second recording stack,
 - 15 - a transparent spacer layer (4) sandwiched between the recording stacks (2, 5), said transparent spacer layer (4) having a thickness substantially larger than the depth of focus of the focused radiation beam (9),
 characterized in that $0.45 \leq T_{L0} \leq 0.75$ and $0.40 \leq R_{L1} \leq 0.80$ and $k_{L0} < 0.3$ and $k_{L1} < 0.3$.
- 20 2. A dual-stack optical data storage medium as claimed in claim 1, wherein λ is approximately 655 nm.
3. A dual-stack optical data storage medium as claimed in claim 1 or 2, wherein for the write-once L_0 recording layer the following conditions are fulfilled $n_{L0} \geq 2.5$ and d_{L0} is
 25 in the range of $\lambda/8n_{L0} \leq d_{L0} \leq 3\lambda/8n_{L0}$ or $5\lambda/8n_{L0} \leq d_{L0} \leq 7\lambda/8n_{L0}$.
4. A dual-stack optical data storage medium as claimed in claim 1 or 2, wherein a first metal reflective layer, having a thickness $d_{M1} \leq 25$ nm, is present between the write-once L_0 recording layer and the transparent spacer layer and d_{L0} is in the range of $\lambda/8n_{L0} \leq d_{L0} \leq$

$5\lambda/8n_{L0}$.

5. A dual-stack optical data storage medium as claimed in claim 4, wherein a first transparent auxiliary layer I1, having a refractive index $n_{I1} \geq 1.8$ and having a thickness $d_{I1} \leq \lambda/2n_{I1}$, is present between the first metal reflective layer and the transparent spacer layer.
6. A dual-stack optical data storage medium as claimed in claim 5, wherein $d_{I1} \leq \lambda/4n_{I1}$.
7. A dual-stack optical data storage medium as claimed in claim 1 or 2, wherein a second transparent auxiliary layer I2, having a refractive index n_{I2} and having a thickness d_{I2} in the range of $0 < d_{I2} \leq 3\lambda/8n_{I2}$, is present at a side of the write-once L_0 recording layer and d_{L0} is in the range of $\lambda/8n_{L0} \leq d_{L0} \leq 3\lambda/8n_{L0}$ or $5\lambda/8n_{L0} \leq d_{L0} \leq 7\lambda/8n_{L0}$.
8. A dual-stack optical data storage medium as claimed in claim 7, wherein the second transparent auxiliary layer (12) is present at a side of the write-once L_0 recording layer (6) most remote from the entrance face (8) and $n_{I2} \leq n_{L0}/1.572$.
9. A dual-stack optical data storage medium as claimed in claim 7, wherein the second transparent auxiliary layer (12) is present at a side of the write-once L_0 recording layer (6) closest to the entrance face and $n_{I2} \geq n_{L0}/0.636$.
10. A dual-stack optical data storage medium as claimed in any one of the preceding claims, wherein a second metal reflective layer (15) is present at a side of the write-once type L_1 recording layer (3) most remote from the entrance face (8).
11. A dual-stack optical data storage medium as claimed in claim 10, wherein the second metal reflective layer (15) has a thickness $d_{M1} \geq 25$ nm.
12. A dual-stack optical data storage medium as claimed in claim 11, wherein d_{L1} is in the range of $0 < d_{L1} \leq 3\lambda/4n_{L1}$.
13. A dual-stack optical data storage medium as claimed in claim 12, wherein a third transparent auxiliary layer I3 (13), having a refractive index n_{I3} and having a thickness

d_{I3} in the range $0 < d_{I3} \leq \lambda/n_{I3}$, is present adjacent the write-once type L_1 recording layer (3) at a side of the write-once type L_1 recording layer closest to the entrance face (8).

14. A dual-stack optical data storage medium as claimed in claim 11, wherein a
5 third metal reflective layer (17), having a thickness d_{M3} in the range of $0 < d_{M3} \leq 25$ nm, is present at a side of the write-once L_1 recording layer (3) closest to the entrance face (8) and d_{L1} is in the range of $0 < d_{L1} \leq 5\lambda/16n_{L1}$ or $7\lambda/16n_{L1} \leq d_{L1} \leq \lambda/n_{L1}$.

15. A dual-stack optical data storage medium as claimed in claim 12 or 14,
10 wherein a fourth transparent auxiliary layer I_4 , having a refractive index n_{I4} and having a thickness d_{I4} in the range of $0 < d_{I4} \leq 3\lambda/16n_{I4}$, is present between the write-once L_1 recording layer (3) and the second metal reflective layer (15).

16. A dual-stack optical data storage medium as claimed in claim 13, wherein a
15 fourth transparent auxiliary layer I_4 , having a refractive index n_{I4} and having a thickness d_{I4} in the range of $0 < d_{I4} \leq 3\lambda/16n_{I4}$, is present between the write-once L_1 recording layer (3) and the second metal reflective layer (15).

17. A dual-stack optical data storage medium as claimed in claim 14 or 15,
20 wherein a fifth transparent auxiliary layer I_5 , having a refractive index n_{I5} and having a thickness d_{I5} in the range of $0 < d_{I5} \leq 3\lambda/16n_{I5}$, is present adjacent the third metal reflective layer (17) at a side of the third metal reflective layer closest to the entrance face (8).

18. A dual-stack optical data storage medium as claimed in any one claims 5, 6, 7,
25 8, 9, 13, 15, 16 or 17, wherein at least one of the transparent auxiliary layers comprises a transparent heatsink material selected from the group of materials ITO, HfN and AlON.

19. A dual-stack optical data storage medium as claimed in claim 1 or 2, wherein a
guide groove (G) for L_1 is provided in the transparent spacer layer (4).

20. A dual stack optical data storage medium as claimed in claim 1 or 2, wherein a
guide groove (G) for L_1 is provided in the substrate (1).

1/11




FIG. 1a




FIG. 1b

2/11




FIG. 2




FIG. 3

3/11




FIG. 4a




FIG. 4b

4/11




FIG. 5




FIG. 6a




FIG. 6b

5/11




FIG. 7a




FIG. 7b

6/11




FIG. 8a




FIG. 8b




FIG. 9

7/11




FIG. 10a




FIG. 10b

8/11




FIG. 11




FIG. 12

9/11




FIG. 13




FIG. 14

10/11




FIG. 15

11/11




FIG. 16a




FIG. 16b

INTERNATIONAL SEARCH REPORT

International Application No

PCT/IB 03/00090

A. CLASSIFICATION OF SUBJECT MATTER

IPC 7 G11B7/24

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 G11B

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

EPO-Internal, PAJ, WPI Data

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	EP 1 118 987 A (SONY CORP) 25 July 2001 (2001-07-25)	1-3
A	column 1, line 25 -column 3, line 33; figures 1-5 column 7, line 18 -column 8, line 39 ---	4-20
Y	US 6 226 239 B1 (NISHIUCHI KENICHI ET AL) 1 May 2001 (2001-05-01)	1-3
A	column 13, line 56 -column 18, line 41 column 41, line 28 -column 42, line 19; figures 1,5 ---	4-20
Y	US 5 627 817 A (ROSEN HAL J ET AL) 6 May 1997 (1997-05-06)	1-3
A	column 4, line 44 -column 10, line 17; figures 1-6 --- -/--	4-20

☒ Further documents are listed in the continuation of box C.☒ Patent family members are listed in annex.

* Special categories of cited documents :

- *A* document defining the general state of the art which is not considered to be of particular relevance
- *E* earlier document but published on or after the international filing date
- *L* document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- *O* document referring to an oral disclosure, use, exhibition or other means
- *P* document published prior to the international filing date but later than the priority date claimed

- *T* later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
- *X* document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
- *Y* document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.
- *&* document member of the same patent family

Date of the actual completion of the international search

24 March 2003

Date of mailing of the international search report

02/04/2003

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax: (+31-70) 340-3016

Authorized officer

Moje, A

INTERNATIONAL SEARCH REPORT

International Application No

PCT/IB 03/00090

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category °	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	US 5 846 627 A (HONG GILBERT H) 8 December 1998 (1998-12-08) column 6, line 12 -column 11, line 56; figures 1,3,6 -----	1-20

INTERNATIONAL SEARCH REPORT

International Application No

PCT/IB 03/00090

Patent document cited in search report		Publication date	Patent family member(s)	Publication date
EP 1118987	A	25-07-2001	JP 2000353338 A	19-12-2000
			AU 5106900 A	02-01-2001
			EP 1118987 A1	25-07-2001
			CN 1320259 T	31-10-2001
			WO 0077783 A1	21-12-2000
US 6226239	B1	01-05-2001	US 6027594 A	22-02-2000
			US 2002150032 A1	17-10-2002
			US 6434095 B1	13-08-2002
			CN 1157048 A	13-08-1997
			EP 1213709 A1	12-06-2002
			EP 1217617 A1	26-06-2002
			EP 0764323 A2	26-03-1997
			WO 9631875 A2	10-10-1996
			JP 10505188 T	19-05-1998
			KR 248096 B1	15-03-2000
			SG 74605 A1	22-08-2000
			SG 74034 A1	18-07-2000
			US 5764619 A	09-06-1998
US 5627817	A	06-05-1997	NONE	
US 5846627	A	08-12-1998	US 5669995 A	23-09-1997